a month from the date of publication of this notice and establish their claims, failing which the said timber will lapse to Government under Section 42 of the said Act.

Locality	Kind	Length	Girth	C.ft.	Kept in the custody of
		Ft. in.	Ft. in.	C.ft.	
1. Sorab Range	Teak ...	9 0	6 6	...	Shiralkoppa timber Depot.
2. Shikarpur Range.	Do ...	10 6	3 4	7	Mr. Ahmed Sheriff Sab, son of the Patel of Ambligola.
	Do ...	5 6	3 6	4	
	Do ...	7 6	2 2	2	
	Do ...	6 9	2 2	2	
	Honne ...	13 4	4 8	18	
	Do ...	13 4	4 0	14	
	Do ...	15 4	3 5	11	
	Do ...	16 5	3 5	12	
	Do ...	13 5	3 2	8	

N. VENKATARAMAIYA,
District Forest Officer.

ENGINEERING DEPARTMENT.

CHITALDRUG DIVISION.

Notice dated 15th May 1939.

Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 5th June 1939, for improving Water Supply to Budihal Sri Rampur Herikere Rg. No. 89 of Hosdurga Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for improving Water Supply to Budihal Sri Rampur Herikere Rg. No. 89 of Hosdurga Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 1,000 (in words) rupees one thousand only in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest. After approval of tender, the balance amount of Rs. 1,930 will have to be paid.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 5th June 1939 at 4 P.M. The final acceptance of the tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days, between 11 A.M. and 5 P.M. and the tender notification, may be obtained from that officer on payment of Re. 1.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer, or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of June 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 50 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and bailing of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. The detail measurements will be taken and paid for all lumpsum items of work.

24. Chamundi Brand cement alone to be used.

Abstract estimate for improving Water Supply to Budihal Sree Rampur Hirekere Major Tank, Reg. No. 89 of Hosdurga Taluk.

Item No.	Details of work	Unit	Rate	Quantity	Rates quoted	
					In words	In figures
			Rs. a. p.			
	A. VIJRA TANK.					
	(1) *Bund.*					
1	Jungle clearing	As per actual work done				
2	Earthwork to bund with watering and tamping including cutting grips ..	C.yd.	0 5 0	1,045		
3	Gravel backing to revetment ..	,,	0 8 0	10		
4	New stone revetment with jelly ..	,,	1 8 0	38		
5	Turfing the slopes of the bund ..	Sqr.	0 12 0	78.20		
6	Supplying and fixing gauge stones ..	Each	15 0 0	2		
7	Supplying and fixing grade stones ..	,,	2 0 0	9		
8	Supplying and fixing Reg. No. stone ..	,,	5 0 0	1		
9	Supplying and fixing B. M. stones ..	,,	5 0 0	2		
	(2) *Breached portion.*					
1	Clearing jungle and roots, etc. ..	As per actual work done				
2	Clearing silt and sand	C.yd.	0 2 0	537		
3	Breaking loose boulders and removing ..	As per actual work done				
4	Earthwork excavation in ordinary soil ..	C.yd.	0 3 0	311		
5	Cutting steps and grips	As per actual work done				
6	Benching rock to seat masonry core wall	S.ft.	0 4 0	300		
7	Constructing masonry core wall ..	C.ft.	0 5 0	960		
8	Constructing puddle wall	C.yd.	0 10 0	1,341		
9	Earthwork to breach with mixture of soils including watering and tamping	C.yd.	0 7 0	10,280		
10	Gravel backing to revetment ..	,,	0 8 0	332		
11	New stone revetment	,,	1 10 0	935		
12	Turfing to slopes	Sqr.	0 12 0	160.05		
13	Bailing out water	As per actual execution				
14	Protective works	As per actual execution				
	(3) *Sluice at R. L.* 154.00.					
1	Earthwork cutting open the bund ..	C.yd.	0 4 0	571		
2	Concrete in surki mortar	C.ft.	0 4 0	1,028		
3	Burnt brink or size stone in surki mortar	,,	0 5 0	2,122		
4	Burnt stone slabs dressed and fixed ..	S.ft.	0 8 0	703		
5	Plastering or pointing in surki mortar	Sqr.	3 8 0	7.46		
6	Drilling holes in slabs	Each	1 0 0	8		
7	Cutting grooves in slabs	Each	..	..		
8	Earthwork refilling with watering and tamping	C.yd.	0 3 0	571		
9	Providing and fixing screw gearing rod with teakwood shutter, etc. ..	Each	..	..		
10	Removing and resetting old stone ..	C.yd.	1 0 0	39		
11	Blocking up the old sluice	As per actuals				
	(4) *Waste Weir. Length* 154'.					
1	Earthwork excavation in hard mixed boulders and soft rock	C.yd.	0 8 0	1,361		
2	Do hard rock ..	,,	2 0 0	100		
3	Concrete in surki mortar	C.ft.	0 4 0	330		
4	Burnt stone in surki mortar	,,	0 5 0	412		
5	Burnt stone slabs dressed and fixed in surki motar	S.ft.	0 8 0	224		
6	Pointing with cement mortar ..	Sqr.	4 0 0	4.26		
7	Rough stone work new with jelly ..	C.yd.	1 8 0	103		

Item No.	Details of work	Unit	Rate	Quantity	Rates quoted	
					In words	In figures
	(4a) Waste Weir Draft Channel.		Rs. a. p.			
1	Excavating a draft channel ..	C.yd.	0 3 0	1,852		
2	Training bank towards bund ..	,,	0 5 0	340		
3	Revetment with jelly backing ..	,,	1 8 0	87		
4	Rough stone wall in halla to protect the rear of breach filling ..	,,	1 8 0	98		
	B. (1) FEEDER CHANNEL.					
	Channel Proper.					
1	Jungle clearing	Mile	10 0 0	3¾		
2	Earthwork excavation in ordinary soil ..	C.yd.	0 3 6	22,170		
3	Forming the bank with lead and consolidation	,,	0 5 0	2,034		
4	Rough stone revetment to Vengalpur and Kachapur tanks wherever necessary	,,	..	..		
5	Providing and fixing mile stone ..	Each	6 0 0	4		
	Do grade stones ..	,,	2 0 0	90		
	Do bed grade stones ..	,,	0 8 0	90		
	(2) *Anicut.*					
1	Earthwork excavation for foundation ..	C.yd.	0 4 0	486		
2	Clearing jungle	As per actual work done				
3	Benching rock	S.ft.	0 4 0	149		
4	Concrete in surki mortar	C.ft.	0 4 0	1,609		
5	Burnt size stone in surki mortar ..	,,	0 5 6	7,213		
6	Burnt stone slab 6″ thick face neatly dressed and fixed in surki mortar ..	S.ft.	0 8 0	1,001		
7	Pointing in surki mortar	Sqrs.	2 8 0	25.52		
8	Joggle joints	Each	0 8 0	66		
9	Cutting grooves to regulate shutters of scouring sluice	R.ft.	..	..		
10	Providing teakwood shutters with screw gearing arrangements	Each	..	..		
11	Rough stone work, new	C.yd.	1 12 0	331		
12	Turfing	Spr.	..	..		
13	Jelly filling below apron	C.yd.	0 8 0	189		
14	Earthwork to flank bund (good spoil from excavation also to be used) ..	C.yd.	0 4 0	815		
15	Bailing out water	As per actual execution				
	(3) *Head Sluice.*					
1	Earthwork excavation	C.yd.	0 4 0	293		
2	Concrete in surki mortar	C.ft.	0 4 0	435		
3	Burnt stone in surki mortar	,,	0 5 0	3,962		
4	Burnt stone slabs 6″ dressed and fixed in surki mortar	S.ft.	0 8 0	287		
5	Surki plastering or painting	Sqr.	3 8 0	8.78		
6	Cutting grooves for the shutters ..	Each	..	..		
7	Providing teakwood shutters with screw gearing arrangements ..	Each	..	..		
8	Side revetment wherever necessary ..	C.yd.	..	..		
9	Earthwork filling between head wall ..	C.yd.	0 4 0	3		
10	Miscellaneous works including bailing out water, etc.	L. S. as per actual work done				

Item No.	Details of work	Unit	Rate	Quantity	Rates quoted	
					In words	In figures
			Rs. a. p.			
	(4) *Relieving Weir*, 100 *feet.*					
1	Earthwork excavation in hard soil ..	C.yd.	0 4 0	147		
2	Concrete in surki mortar	C.ft.	0 4 0	650		
3	Burnt brick or stone in surki ..	,,	0 5 0	1,291		
4	Surki plastering or pointing	Sqr.	3 8 0	11.85		
5	Rough stone work	C.yd.	1 12 0	60		
	(5) *Relieving Weir* 55 *feet.*					
1	Earthwork excavation in hard soil ..	C.yd.	0 4 0	86		
2	Surki concrete	C.ft.	0 4 0	381		
3	Burnt stone in surki mortar	,,	0 5 0	701		
4	Surki plastering or pointing ...	Sqr.	3 8 0	5.55		
5	Rough stone apron	C.yd.	1 12 0	35		
	(6) *Masonry Drop* 6 *feet. No.* 1.					
1	Earthwork excavation in hard soil ..	C.yd.	0 4 0	51		
2	Surki concrete	C.ft.	0 4 0	159		
3	Burnt brick or size stone in surki mortar	,,	0 5 0	432		
4	Burnt stone slabs dressed and fixed ..	S.ft.	0 8 0	51		
5	Jelly filling below	C.yd.	0 8 0	3		
6	Rough stone work	,,	1 12 0	11		
7	Plastering or pointing with in surki mortar	Sqr.	3 8 0	3.45		
	(7) *Masonry Drop* 6 *feet same as No.* 1.					
	(8) *Masonry Drop of* 5 *feet.*					
1	Earthwork excavation in hard soil ..	C.yd.	0 4 0	46		
2	Surki concrete	C.ft.	0 4 0	152		
3	Burnt brick or size stone in surki mortar	,,	0 5 0	365		
4	Burnt stone slabs 4" to 6" dressed and fixed	S.ft.	0 8 0	51		
5	Jelly filling	C.yd.	0 8 0	3		
6	Rough stone work	,,	1 12 0	11		
7	Plastering or pointing with surki mortar	Sqr.	3 8 0	2.95		
	(9) *Masonry Drop of* 4 *feet.*					
1	Earthwork excavation in hard soil ..	C.yd.	0 4 0	41		
2	Concrete in surki mortar	C.ft.	0 4 0	146		
3	Burnt brick or size stone in surki mortar	,,	0 5 0	302		
4	Burnt stone slabs dressed and fixed in surki mortar	S.ft.	0 8 0	51		
5	Jelly filling	C.yd.	0 8 0	3		
6	Rough stone work	,,	1 12 0	11		
7	Plastering or pointing with surki mortar	Sqrs.	3 8 0	2.45		
	(10) *Masonry Drop of* 2 *feet same as above* ..	..	..	..		

Notification dated 21*st May* 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 31st May 1939, for (1) Restoring Kodihally Minor Tank, Hosdurga Taluk, and (2) Restoring Basapura Tank, Challakere Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as " Tender for Restoring Kodihally Minor Tank, Hosdurga Taluk, and (2) Restoring Basapura Tank, Challakere Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 100 each (in words) rupees one hundred only for each in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 31st May 1939 at 4 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days, between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Re. 1.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 10 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

2. The contractor should arrange for the payment of royalty and tolls.

Note.—(a) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary, provide for the same by insurance at the proper time.

(b) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. Details will be measured and paid for all lumpsum items of work.

24. Chamundi Brand cement alone have to be used.

(1) Estimate for restoring Kodihally Tank Reg. No. 67 of Hosdurga Taluk; and
(2) Estimate for restoring Basapura Tank.

Absract estimate for restoring Kodihally Minor Tank, Reg. No. 67 of Hosdurga Taluk.

Item No.	Details of work	Unit	Rate	Quantity	Rates quoted	
					In words	In figures
	I. Bund.		Rs. a. p.			
1	Earthwork to bund including watering and tamping	C.yd.	0 5 0	2,683		
2	Turfing to slopes of bund	S.yd.	0 1 0	2,317		
3	Cutting grips	Grade	1 0 0	22		
4	Jungle clearing	As per actuals				
5	Resetting old stone revetment wherever damaged	As per actuals				
6	Providing new stone revetment	C.yd.	1 8 0	104		
7	Removing and refixing grade stones	Each	0 2 0	18		
8	Providing new grade stones	,,	2 0 0	7		
9	Providing top width stone	,,	0 8 0	25		
10	Providing Number stone	,,	5 0 0	1		
11	Providing B. M. Stones	,,	2 0 0	2		
	II. Sluice.					
1	Earthwork excavation	C.yd.	0 3 0	87		
2	Jelly concrete in lime mortar	C.ft.	0 4 0	113		
3	Size stone in lime mortar	,,	0 4 0	192		
4	Cement pointing	Sqr.	4 0 0	1.68		
5	Cement concrete coping	C.ft.	0 12 0	10		
6	Providing plug and rod including locking arrangements	Each	..	..		
7	Cutting orifices	,,	..	..		
8	Cement plastering	Sqr.	8 0 0			
9	Earthwork refilling including watering and tamping, etc.		0 3			
10	Providing 6" diameter cast					

Item No.	Details of work	Unit	Rate	Quantity	Rates quo	
					In words	In
	III. Waste Weir.		Rs. a. p.			
1	Earthwork excavation	C.yd.	0 3 0	512		
2	Size stone in lime mortar	C.ft.	0 4 0	677		
3	Coping with cement concrete ..	,,	0 12 0	97		
4	Removing and resetting old stone apron	C.yd.	0 12 0	26		
5	Providing new stone apron	,,	1 8 0	118		
6	Benching rock	S.ft.	0 2 0	197		
7	Size stone in mortar	C.ft.	0 4 0	803		
8	Coping with cement concrete ..	,,	0 12 0	23		

Abstract estimate for restoring Basapura Tank, Challakere Taluk.

	I. Bund.					
1	Clearing jungle on top and slopes of bund, cutting trenches, etc., complete ..	As per actuals				
2	Earthwork to bund including watering and consolidation	C.yd.	0 5 0	2,612		
3	Rough stone revetment with jelly backing and wedging, etc., complete ..	,,	1 8 0	799		
4	Turfing the slopes of bund	S.yd.	0 1 0	2,227		
5	Providing grade stones with carving figures, painting, etc., complete ..	Each	2 0 0	12		
6	Providing new B. M. stones	,,	3 8 0	2		
7	Providing new Reg. No. stone ..	,,	5 0 0	1		
8	Providing new gauge stone	,,	10 0 0	1		
	II. Waste Weir including draft and approach cuts.					
1	Earthwork excavation	Charged under earthwork for bund				
2	Size stone in surki mortar	C.ft.	0 5 0	314		
3	Casting cement concrete slab (1 : 2 : 4) ..	,,	0 12 0	51		
4	Rough stone apron with jelly backing and wedging, etc., complete	C.yd.	1 8 0	42		
5	Draft and approach cuts	Charged under earthwork for bund				
	III. Sluice.					
1	Earthwork excavation	Charged under earthwork for bund				
2	Stone jelly in surki mortar	C.ft.	0 4 6	115		
3	Size stone in surki mortar	,,	0 5 0	175		
4	Cement mortar (1 : 3) plastering ½" thick	Sqr.	6 0 0	39		
5	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar ..	S.ft.	0 8 0	22		
6	Providing, laying and fixing C. I. pipes, 9" diameter	Cwt.	9 0 0	..		
7	Providing iron rod with plug lock, key, etc., complete and boring hole in the slab	Each	..	..		
8	Cement pointing to exposed portions ..	Sqr.	4 0 0	2		

S. RAMASWA
Executive Eng

MISCELLANEOUS DEPARTMENTS.

INDIAN POSTS AND TELEGRAPHS DEPARTMENT.

SUPERINTENDENT OF POST OFFICES, BANGALORE DIVISION.

...onveyan... ...otor vehicles daily between Ba...
...ar ...sidy for a period of three yea...
...d at present is 36 miles.